

APPENDIX 26

Cost Estimates for South Park Lands / Glenside detention basins



PVICTORIA PARK WETLANDS PRELIMINARY DESIGN

ESTIMATE SUMMARY

CONTRACTOR COSTS	This rev
PRELIMINARIES	\$1,417,913
DEMOLITION, SEWER ALTERATIONS AND EARTHWORKS	\$3,208,520
CLAY LINING AND GROWING MEDIUM	\$481,559
INLET AND OUTLET STRUCTURES	\$366,581
PLANTING, IRRIGATION, MAINTENANCE AND PATHS	\$1,132,412
DEMOB	\$27,000
CONTRACTORS OH	\$530,719
TOTAL CONTTACTORS COSTS	\$7,164,704
CLIENT COSTS	
EXISTING SERVICES IDENTIFICATION & ALTERATIONS	\$71,647
PROJECT PLANNING	\$429,882
DESIGN AND INVESTIGATIONS	\$1,003,059
PROJECT & CONTRACT MANAGEMENT	\$573,176
COMMUNITY ENGAGEMENT & LIASON	\$143,294
TOTAL CLIENT COSTS	\$2,221,058
RISK AND CONTINGENCY	
Inherent and Contingent risk	\$2,064,868
PROJECT TOTAL	\$11,450,630

KEY ASSUMPTIONS

Assumes no Hardscaping, path lighting or structures

Assumes all contaminated materials buried in fill mounds

Assumes (conservatavely) that 50% of floor (post reworking and compacting) will be suitable for retaining water and the balance will require suitable clays won from the excavation.

Assumes No land acquisition

Excludes escalation, prices current at Jan 2015

Excludes works associated with additional contaminated materials that may be stockpiled on site by ACC (refer Tonkins report cl. 12.2.3)



SOUTH PARK LANDS STORMWATER MANAGEMENT

COST ESTIMATE FOR VICTORIA PARK WETLANDS & DETENTION STORAGE PRELIMINARY DESIGN

				COSTPLAN QTYS AND COS		
ITEM	DESCRIPTION CONTRACT WORKS COSTS		QUANTITY	RATE	AMOUNT	COMMENTS
1	Preliminaries and overheads					
1.1	Establishment including contractors onsite overheads	% calc	15.2%	\$5,667,089	\$859,932	includes mobilisation, supervision, insurances and fees, site accommodation, preparation of Project management plans etc.
1.2	Materials and Geotechnical Testing	item	1	\$50,000	\$50,000	Including geotechnical and concrete
	Environmental management					including dust and sediment testing, auditing and associated testing requirements
1.3	Environmental controls	item	1	\$68,000	\$68,000	
1.4	Environmental maintenance	item	1	\$26,964	\$26,964	
	2. W. C. W. C. W. C. W. C.	KOIII	·	\$25,501	Ψ20,001	
1.5	Survey Setout and abuilding	item	1	\$120,960	\$120,960	Minimal ,utilise GPS fitted plant. Allow for asbuilds
1.6	Traffic and pedestrian management	item	1	\$163,649	\$163,649	Includes signage, temporary diversions traffic management crews, audits etc.
1.7	Temporary and project fencing	m	1,592	\$25.00	\$39,800	Project perimeter plus excluded zones
1.8	Temporary access tracks and hardstands	m2	4,800	\$15.96	\$76,608	Includes reinstatement
1.9	Indigenous monitoring for artifacts etc (while topsoil strip works being performed)	Hrs	160	\$75	\$12,000	allows for 2 men x 2 weeks
	Subtotal Section 1				\$1,417,913	
2	Demolition & Earthworks					
2.1	Sewer Relocation					
2.1.1	Remove Existing Sewer Pipe	lm	125	\$45	\$5,625	
2.1.2	New 900 Dia Manhole, 3000 deep	No	2	\$4,815	\$9,630	
2.1.3	New 900 Dia Manhole over existing main	No	2	\$7,315	\$14,630	
2.1.4	New 225mm UPVC Pipe	lm	168	\$325	\$54,600	
2.1.5	Testing	item	1	\$1,500	\$1,500	
2.2	General Demolition / Early works					
2.2.1	Relocate Existing Gym Equipment	Item	1	\$6,000	\$6,000	
2.2.2	Tree Removal	item	1	\$18,000.00	\$18,000	36 total, 4 wetland and 32 batter
2.2.3	Stand of Poplars Removed	item	1	\$20,558.40	\$20,558	Incl poisoning to prevent suckering
2.2.4	General site clearing and Grubbing	m2	93,356	\$0.16	\$14,937	
	<u>Earthworks</u>					Assumes contaminated materials buryed on site in fill mounds. Refer EW analysis
2.3	Strip Topsoil	m3	9,336	\$2.75	\$25,673	Assume 100mm thick (Assume able to be reused / stored onsite)
2.3.1	Stockpile management	item	1	\$97,500	\$97,500	Preparation of areas for storage of materials for enviro classification, and local dust control of these
2.3.2	Cut to stockpile for testing and classification,(horizon H1 materials - previous fill)	BCM	57,771	\$2.75	\$158,870	
2.3.3	Testing for contaminants	BCM	57,771	\$2.00	\$115,542	
2.3.4	Fill mounds from stockpile	CCM	24,574	\$4.10	\$100,753	Utilise ILC and LLC materials first
2.3.6	Surplus horizon H1 WFC fills to offsite dump	BCM	48,488	\$20.31	\$984,782	Load and cart to Gillman area , 21 KM lead
2.3.5	Cut to stockpile H2 materials suitable for clay liner	BCM	9,283	\$2.75	\$25,529	
2.3.7	Cut to spoil direct balance of H2 materials	BCM	67,399	\$21.95	\$1,479,409	Load and cart to Gillman area , 21 KM lead
2.3.8	Trim Batter Slopes	m2	43,650	\$0.92	\$40,158	
2.3.9	Respread previously stripped topsoil	m3	9,336	\$3.73	\$34,822	From stockpiles
	Subtotal Section 2				\$3,208,520	\$6,946
3	Basin Lining				40,200,020	Conservatively assumes 50% of subgrade is suitable insitu
3.1	Trim & Compact Basin for lining	m2	42199	\$1.21	\$51,061	approx. 50% remains
3.2					\$55,954	assume 50%
3.4	Fill from stockpile select clay lining material Supply and Place300mm Thick Growing Medium, Compacted to 85%	CCM m2	8,440 34205	\$6.63 \$10.95	\$374,545	to Max Active Storage Level excluding the deep ponds
	Subtotal Section 3		0 1200	Ų10.00	\$481,559	to man some control of the control o
4	Drainage structures, Inlet / Outlet				\$401,335	
4.1	Creek Culvert					
4.1.1	Demolition & Remove Existing Pipe & Headwalls	item	1	\$4,500	\$4,500	
4.1.2	New 1350 Dia RCP, Class 2	lm	23	\$960	\$22,080	
4.1.3	Precast Concrete Headwalls to Suit 1350 RCP	no	2	\$18,000	\$36,000	
4.2	Inlet Structures					
		item	11	\$4,800 \$18,000	\$4,800 \$18,000	
4.2.1	Clear / Trim Existing Creek Concrete Inlet Structure with Grate to suit 675mm RCP	item			Ψ10,000	i e
4.2.1 4.2.2 4.2.3	Concrete Inlet Structure with Grate to suit 675mm RCP	item no	1	\$12,450	\$12,450	
4.2.2					\$12,450 \$1,800	
4.2.2 4.2.3	Concrete Inlet Structure with Grate to suit 675mm RCP 1500 SQ Junction Box with Drop Gate	no	1	\$12,450		



SOUTH PARK LANDS STORMWATER MANAGEMENT

COST ESTIMATE FOR VICTORIA PARK WETLANDS & DETENTION STORAGE PRELIMINARY DESIGN

777.44	DECODITION		OLIAN TETP	COSTPLAN QTYS AND CO		COMPENSO
### 4.3	DESCRIPTION 200mm Spillway Slab (2m x 25m)	m2	QUANTITY 50	RATE \$235	\$11,750	COMMENTS including edge footing
4.3.1	200mm Concrete Weir Wall	m2	15.52	\$360	\$5,587	Incidently dage rooting
4.3.2	Rock Facing to Concrete Walls	m2	31.04	\$240	\$7,450	both sides
4.3.3	Fill & Regrade to Match New Structures	item	1	\$5,400	\$5,400	
4.3.4	Rock Scour Protection	m3	91	\$95	\$8,645	
4.4	Outlet Structures					
4.4.1	Clear / Trim Existing Creek	item	1	\$4,800	\$4,800	
4.4.2	Concrete Outlet Structure 7m L x 0.9m W x 0.95m D, Suit 900 RCP	item	1	\$24,000	\$24,000	
4.4.3	1500 SQ Junction Box With light Duty Grate and Flap Gate Valve	no	1	\$12,450	\$12,450	Flap Gate Valve to Suit 900 RCP, Upstream Face
4.4.4	Precast Headwall to Suit 900mm RCP	no	1	\$2,450	\$2,450	
4.4.5	900mm RCP,Class 2 Inlet pipe	lm	17.3	\$481	\$8,321	
4.4.6	Stone Pitching around Outlet Structure	m2	128	\$95	\$12,160	
4.5	Spill Way					
4.5.1	A34 Geotextile	m2	756	\$3.00	\$2,268	
4.5.2	300mm thick Reno Mattress	m2	690	\$150	\$103,500	Fill Between Stone with Friable Sandy loam
4.5.3	200W x 600D N32 Concrete Edge Beam w/N16 Reo Bars	lm	110	\$135	\$14,850	
4.5.4	Footpath over Embankment/Spillway, 100mm thick x 3.6m wide	m2	198	\$145	\$28,710	
	Cubtotal Castion 4				\$200 E04	
	Subtotal Section 4				\$366,581	
5	Landscaping works					
5.1	Establishment / Maintenance and wetlands top up planting for Landscaping works	item	1	\$157,000	\$157,000	Assume 1 yr. maintenance period
5.2	Aquatic and wetland Species	m2	30433	\$10.50	\$319,547	Excludes netting, assume virocell @ 3/m2 on average
5.3	Dryland Grass Mix	m2	57226	\$1 CE	\$04.400	Agguera budra agget
5.4	New Tree plantings	m2 no	786	\$1.65 \$90.00	\$94,423 \$70,740	Assume hydro seed assume 45 litre trees
5.5	Mulched Planting Bed	m2	676	\$31.00	\$20,956	Allow for the recycling of select tree removals(native) as mulch
5.6	Planting Bed in 300 reno matt	m2	110	\$50.00	\$5,500	
5.7 5.8	Irrigation to planting beds and trees only Primary Pathway - 3m Sealed	item m2	1 6105	\$36,930.00 \$64.54	\$36,930 \$393,996	temporary and for establishment period SG prep, 200 CR, prime and 40 AC10+edges+ line marking
5.9	Secondary Pathway - 1.8m Rubble	m2	734.4	\$40.47	\$29,720	SG prep, 150 QR +edges
5.10	Signage	No	12	\$300.00	\$3,600	Token
	Lighting	EVOLUE	ED EDOM E	TIMATE		
	Lighting Street and Park furniture		ED FROM ES ED FROM ES			
	Structures and Retaining walls	EXCLUD	ED FROM ES	TIMATE		
	Wetlands edge restraint	EXCLUD	ED FROM ES	TIMATE		
	Subtotal Section 5				\$1,132,412	\$971,812
6	Reinstatement and finishing works				71,112,112	40.1,01
	-					
6.3	Site clean-up and demobilisation	item	1	\$27,000	\$27,000	
				L		I
	Subtotal Section 6				\$27,000	
	Subtotal Section 6				\$27,000	\$5.546.12S
	Subtotal Section 6 SUBTOTAL 1 - 6				\$27,000 \$6,633,985	\$5,546,126
						\$5,546,129
7	SUBTOTAL 1 - 6					\$5,546,129
7	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin				\$6,633,985	
7	SUBTOTAL 1 - 6	%	8%	\$6,633,985		\$5,546,129
	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin	%	8%	\$6,633,985	\$6,633,985 \$530,718.84	
	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin	%	8%	\$6,633,985	\$6,633,985	
7.1	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS	%	8%	\$6,633,985	\$6,633,985 \$530,718.84	
	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin	%	8%	\$6,633,985	\$6,633,985 \$530,718.84	allowance for offsite OH and profit
7.1	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS	%	8%	\$6,633,985 \$7,164,704	\$6,633,985 \$530,718.84	
7.1 8 8.1	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works	%	1%	\$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704	allowance for offsite OH and profit
7.1	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS				\$6,633,985 \$530,718.84 \$7,164,704	allowance for offsite OH and profit
7.1 8 8.1	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works	%	1%	\$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704	allowance for offsite OH and profit
7.1 8 8.1 8.2 8.3	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design	% % %	1% 6% 14%	\$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059	allowance for offsite OH and profit Gap Pipeline
7.1 8 8.1 8.2	SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works	%	1% 6%	\$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882	allowance for offsite OH and profit Gap Pipeline
8 8.1 8.2 8.3 8.4	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management	% % %	1% 6% 14%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176	allowance for offsite OH and profit Gap Pipeline
8 8.1 8.2 8.3 8.4 8.5	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison	% % %	1% 6% 14%	\$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing
8 8.1 8.2 8.3 8.4	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management	% % %	1% 6% 14%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176	allowance for offsite OH and profit Gap Pipeline
8 8.1 8.2 8.3 8.4 8.5	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition	% % %	1% 6% 14% 8% 2%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing
8 8.1 8.2 8.3 8.4 8.5	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison	% % %	1% 6% 14%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing
8 8.1 8.2 8.3 8.4 8.5	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS	% % %	1% 6% 14% 8% 2%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing
8 8.1 8.2 8.3 8.4 8.5	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition	% % %	1% 6% 14% 8% 2%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing
8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST	% % %	1% 6% 14% 8% 2%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing
8.8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST RISK AMD OPPORTUNITY	% % % %	1% 6% 14% 8% 2%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294 \$2,221,058	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing EXCLUDED FROM THIS ESTIMATE
8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST	% % %	1% 6% 14% 8% 2%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing
7.1 8 8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST RISK AMD OPPORTUNITY Inherent Risk	% % % %	1% 6% 14% 8% 2% 31%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294 \$2,221,058 \$9,385,763 \$657,003	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing EXCLUDED FROM THIS ESTIMATE This is the uncertainties in the known or planned scope of the project. These are risks due to unmeasured items and are conditional, i.e. they may or may not
8.8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST RISK AMD OPPORTUNITY	% % % %	1% 6% 14% 8% 2%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294 \$2,221,058	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing EXCLUDED FROM THIS ESTIMATE This is the uncertainties in the known or planned scope of the project.
7.1 8 8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST RISK AMD OPPORTUNITY Inherent Risk Contingent Risk	% % % %	1% 6% 14% 8% 2% 31%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294 \$2,221,058 \$9,385,763 \$657,003 \$1,407,864	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing EXCLUDED FROM THIS ESTIMATE This is the uncertainties in the known or planned scope of the project. These are risks due to unmeasured items and are conditional, i.e. they may or may not
7.1 8 8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST RISK AMD OPPORTUNITY Inherent Risk	% % % %	1% 6% 14% 8% 2% 31%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294 \$2,221,058 \$9,385,763 \$657,003	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing EXCLUDED FROM THIS ESTIMATE This is the uncertainties in the known or planned scope of the project. These are risks due to unmeasured items and are conditional, i.e. they may or may not
7.1 8 8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST RISK AMD OPPORTUNITY Inherent Risk Contingent Risk TOTAL RISK ALLOCATION	% % % %	1% 6% 14% 8% 2% 31%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294 \$2,221,058 \$9,385,763 \$657,003 \$1,407,864 \$2,064,868	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing EXCLUDED FROM THIS ESTIMATE This is the uncertainties in the known or planned scope of the project. These are risks due to unmeasured items and are conditional, i.e. they may or may not
7.1 8 8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST RISK AMD OPPORTUNITY Inherent Risk Contingent Risk	% % % %	1% 6% 14% 8% 2% 31%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294 \$2,221,058 \$9,385,763 \$657,003 \$1,407,864	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing EXCLUDED FROM THIS ESTIMATE This is the uncertainties in the known or planned scope of the project. These are risks due to unmeasured items and are conditional, i.e. they may or may not
7.1 8 8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST RISK AMD OPPORTUNITY Inherent Risk Contingent Risk TOTAL RISK ALLOCATION	% % % %	1% 6% 14% 8% 2% 31%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294 \$2,221,058 \$9,385,763 \$657,003 \$1,407,864 \$2,064,868	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing EXCLUDED FROM THIS ESTIMATE This is the uncertainties in the known or planned scope of the project. These are risks due to unmeasured items and are conditional, i.e. they may or may not
8.8.1 8.2 8.3 8.4 8.5 8.6	Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS Existing services identification and alteration works Project Planning works Investigations and design Project and contract management Community engagement and liaison Land acquisition TOTAL CLIENT COSTS BASE PROJECT COST RISK AMD OPPORTUNITY Inherent Risk Contingent Risk TOTAL RISK ALLOCATION	% % % %	1% 6% 14% 8% 2% 31%	\$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704 \$7,164,704	\$6,633,985 \$530,718.84 \$7,164,704 \$71,647 \$429,882 \$1,003,059 \$573,176 \$143,294 \$2,221,058 \$9,385,763 \$657,003 \$1,407,864 \$2,064,868	allowance for offsite OH and profit Gap Pipeline Including design verification works and Enviro auditing EXCLUDED FROM THIS ESTIMATE This is the uncertainties in the known or planned scope of the project. These are risks due to unmeasured items and are conditional, i.e. they may or may no



BROWN HILL KESWICK CREEK STORMWATER PROJECT SOUTH PARK LANDS STORMWATER MANAGEMENT

COST ESTIMATE FOR VICTORIA PARK WETLANDS & DETENTION STORAGE PRELIMINARY DESIGN

		COSTPLAN QTYS AND COST						
ITEM	DESCRIPTION	QUANTITY	RATE	AMOUNT	COMMENTS			

	IMPORTANT NOTES AND KEY ASSUMPTIONS
1	Excludes GST
2	Costs are current as at Q1, 2015 and excludes escalation
3	Based on TONKIN Preliminary concept design FOR Victoria Park 20130167_Sht01-10-Rev 3& 4.pdf
4	Assumes no Hardscaping, path lighting or structures
5	Assumes all contaminated materials buried in fill mounds
6	Assumes (conservatavely) that 50% of floor (post reworking and compacting) will be suitable for retaining water and the balance will require suitable clays won from the excavation.
7	Assumes No land acquisition
8	Excludes works associated with additional contaminated materials that may be stockpiled on site by ACC (refer Tonkins report cl. 12.2.3)
9	This estimate has been prepared solely for BHKC stormwater authority, C/O the City of Unley . Under no circumstances shall it be passed onto any third parties without the written consent of Costplan Pty Ltd




BROWN HILL KESWICK CREEK STORMWATER PROJECT SOUTH PARK LANDS STORMWATER MANAGEMENT

his revision prepared Jan 2015

EARTHWORKS QUANTITY ANALYSIS FOR VICTORIA PARK WETLANDS & DETENTION STORAGE


ITEM	DESCRIPTION	UOM	QTY		NOTES
Note	Quantities from DC amended 2 take-off				
1 2 3 4	Nett Cut (exclusive of topsoil strip, Topsoil respread, growing medium and clay box out) plus cut fill interface 0.5m zone Less 50% of clay liner, assume reworked Insitu Total nett cut therefore =	BCM BCM	138,295 4,598 -8,440 134,454		
5 6 7	Upper horizon H1 of fill materials (area of contamination) Plus 0.5m interface zone above Total nett H1 therefore =	BCM BCM BCM	53,173 4,598 57,771		
8	Leaves balance of excavation (Horizon 2, natural materials) at	BCM	76,683		
9	For Clay liner salvage following vol of suitable clays from H2	ССМ	8,440		
12 13 14 15	Fill required for mounds Fill required to replace 0.5m interface zone Total fill required Based on review of enviro report , in particular Cl 2.5.3 we can interpret the follow Quantity of samples that meets WFC Quantity of samples that was ILC	82% 15%	19,976 4,598 24,574		100 out of 121 samples (for PAH, note for HM contamination considerably lower) 18 out of 121 samples
16	Quantity of samples that was LLC	3%			3 out of 121 samples
17	So for H1 materials we can adopt			what if ILC and LLC QUANTITYS double	
18 19 20	for WFC (waste fill criteria) for ILC (intermediate level contamination) for LLC (low level contamination)	BCM BCM BCM	47,372 8,666 1,733	36,973 17,331 3,466	} still room to contain onsite in mound if these quantities doubled
21	Strategy is therefore to Bury ILC and LLC in fill mounds and only cart WFC materi	als to dun	np (therefore	no dump fees)	

BROWN HILL KESWICK CREEK STORMWATER PROJECT VICTORIA PARK 3D Report Proposed



BROWN HILL KESWICK CREEK STORMWATER PROJECT VICTORIA PARK Grid Report (50mx50m Grid)


Proposed




Area: Site Perimeter (Batter Edges), Intersection Point: Lower Left Corner, X Grid: 164, Y Grid: 164, Average Haul Distance: 361.8 m

LEGEND


Cut / Fill Depth



BROWN HILL KESWICK CREEK STORMWATER PROJECT PARK 20 3D REPORT Proposed



GRID REPORT (20mx20m Grid) Proposed



Area: Site Perimeter, Intersection Point: Lower Left Corner, X Grid: 65, Y Grid: 65, Average Haul Distance: 199.1 m

LEGEND

Cut / Fill Depth



PARK 20 EMBANKMENT PRELIMINARY DESIGN

ESTIMATE SHMMADY

ESTIMATE SUMMARY	REVISION 3, 29/01/15
	Rev3
CONTRACTOR COSTS	
PRELIMINARIES	\$390,897
DEMO AND EARTHWORKS	\$218,687
EXISTING CREEK REINSTATEMENT	\$68,559
DRAINAGE STRUCTURES	\$408,140
MISC WORKS AND LANDSCAPING	\$219,670
REINSTATEMENT	\$24,000
CONTRACTORS OH	\$106,396
TOTAL CONTTACTORS COSTS	\$1,436,349
CLIENT COSTS	
EXISTING SERVICES IDENTIFICATION & ALTERATIONS	\$28,727
PROJECT PLANNING	\$86,181
DESIGN AND INVESTIGATIONS	\$172,362
PROJECT & CONTRACT MANAGEMENT	\$114,908
COMMUNITY ENGAGEMENT & LIASON	\$28,727
TOTAL CLIENT COSTS	\$430,905
RISK AND CONTINGENCY	
Inherent and Contingent risk	\$410,796
PROJECT TOTAL	\$2,278,049
KEY ASSUMPTIONS	
Assumes No Hardscaping, path lighting or structures	
Assumes No land acquisition	
Excludes escalation, prices current at Jan 2015	



SOUTH PARK LANDS STORMWATER MANAGEMENT

COST ESTIMATE FOR PARK 20 EMBANKMENT PRELIMINARY DESIGN

ITEM	DESCRIPTION CONTRACT WORKS COSTS		QUANTITY	COSTPLAN QTYS AND CO	AMOUNT	COMMENTS
1	Preliminaries and overheads					
1.1	Establishment including contractors onsite overheads	item	15.2%	\$1,144,056	\$173,897	includes mobilisation, supervision, insurances and fees, site accommodation preparation of Project management plans etc.
1.2	Testing	item	1	\$15,000	\$15,000	Including geotechnical, Level one supervision and the supply and installation of dam monitoring equipment
1.3	Environmental controls	item	1	\$35,000	\$35,000	including dust and sediment testing, auditing and associated testing
1.4	Survey Setout and abuilding	item	1	\$25,000	\$25,000	requirements
1.5	Traffic and pedestrian management	item	1	\$85,000	\$85,000	Includes signage, temporary diversions traffic management crews, audits etc
1.6	Temporary and project fencing	m	1	\$15,000	\$15,000	
1.7	Temporary access tracks and hardstands	item	1	\$30,000	\$30,000	
1.9	Indigenous monitoring (while topsoil strip works being performed)	Hrs	160	\$75	\$12,000	allows for 2 men x 2 weeks
	Subtotal Section 1			*****	\$390,897	0.188459304
2	Demolition & Earthworks				+++++++++++++++++++++++++++++++++++++	
	General Demolition / Early works					
2.5	Protection of Toilet Block During construction	Item	1	\$5,000	\$5,000	
2.6	Protection of Trees	Item	1	\$15,000	\$15,000	Assume minor fencing around some of the bigger trees, not specified
2.8	Tree Removal	No	1	\$43,500	\$43,500	53 Batter and 34 Swale Poplars
2.9	Clearing and Grubbing	m2	13930	\$1.20	\$16,716	
2.9	Relocate Existing Headwall and Existing Drainage pipe to Discharge to new	item	1	\$3,500	\$3,500	Sheet 104, Assume 20-30m additional pipe required?
	creek Diversion. Inc. Rock pitching reinstatement hunter HW Earthworks					
2.10	Strip Topsoil	m3	1393	\$9.00	\$12,537	Assume 100mm thick
	Bulk Cut to Fill	m3	4239	\$12.00	\$50,868	
2.12	Bulk Cut to Spoil	m3	1501	\$25.21	\$37,840	
2.16	Trim Batter Slopes	m2	10309	\$1.65	\$17,010	
2.17	Respread 100mm topsoil	m3	1393	\$12.00	\$16,716	
	Subtotal Section 2				\$218,687	
3	Existing Creek reinstatement					
	Existing Creek with Subsurface Drainage					
3.1	Shape existing Creek Bed	m2	1865	\$ 5	\$9,325	
3.2	Aggregate Bedding (13mm)	m3	44	\$95	\$4,174	150mm thick cover to top and side of pipe, 0.5m wide
3.3	160mm CLASS 400 Slotted Drain coil pipe	lm	303	\$25	\$7,575	
3.4	150mm PVC DWR Riser with Screw Cap, 50m Spacing	lm	15	\$75	\$1,125	2.5m each
3.5	Light Duty Cover and Frame to 150mm PVC risers	no	6	\$1,200	\$7,200	
3.6	65mm Rock Ballast	m3	230.9	\$75	\$17,316	Fill to 300mm above top of aggregate bedding
3.6	65mm Rock Ballast A34 Geotextile	m3 m2	230.9 818.1	\$75 \$3	\$17,316 \$2,454	allowed additional 0.5m for each side
3.6 3.7 3.8	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95%	m3 m2 m3	230.9 818.1 1382.7	\$75 \$3 \$12	\$17,316 \$2,454 \$16,592	
3.6	65mm Rock Ballast A34 Geotextile	m3 m2	230.9 818.1	\$75 \$3	\$17,316 \$2,454	allowed additional 0.5m for each side
3.6 3.7 3.8	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread	m3 m2 m3	230.9 818.1 1382.7	\$75 \$3 \$12	\$17,316 \$2,454 \$16,592 \$2,798	allowed additional 0.5m for each side
3.6 3.7 3.8 3.9	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3	m3 m2 m3	230.9 818.1 1382.7	\$75 \$3 \$12	\$17,316 \$2,454 \$16,592	allowed additional 0.5m for each side
3.6 3.7 3.8	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls	m3 m2 m3	230.9 818.1 1382.7	\$75 \$3 \$12	\$17,316 \$2,454 \$16,592 \$2,798	allowed additional 0.5m for each side
3.6 3.7 3.8 3.9	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert	m3 m2 m3	230.9 818.1 1382.7	\$75 \$3 \$12	\$17,316 \$2,454 \$16,592 \$2,798	allowed additional 0.5m for each side utilise stockpiled spoil
3.6 3.7 3.8 3.9 4	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900	m3 m2 m3 m3	230.9 818.1 1382.7 186.5	\$75 \$3 \$12 \$15	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559	allowed additional 0.5m for each side
3.6 3.7 3.8 3.9 4 4.1 1	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC	m3 m2 m3 m3	230.9 818.1 1382.7 186.5	\$75 \$3 \$12 \$15	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115
3.6 3.7 3.8 3.9 4 4.1 1 2	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units	m3 m2 m3 m3	230.9 818.1 1382.7 186.5	\$75 \$3 \$12 \$15 \$3,000 \$2,570	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840	allowed additional 0.5m for each side utilise stockpiled spoil
3.6 3.7 3.8 3.9 4 4.1 1	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC	m3 m2 m3 m3	230.9 818.1 1382.7 186.5	\$75 \$3 \$12 \$15	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115
3.6 3.7 3.8 3.9 4 4.1 1 2 3	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert Demoilsh Existing Culvert Demoilsh Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units Insitu Concrete Headwall to Suit Twin 1200x900 RCBC	m3 m2 m3 m3 item lm item	230.9 818.1 1382.7 186.5	\$75 \$3 \$12 \$15 \$3,000 \$2,570 \$12,000	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840 \$12,000	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115
3.6 3.7 3.8 3.9 4 4.1 1 2 3 4 5 6	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units Insitu Concrete Headwall to Suit Twin 1200x900 RCBC Concrete Trash Deflector Grouted Stone Pitching New Headwall Barrier	m3 m2 m3 m3 item lm item item	230.9 818.1 1382.7 186.5	\$75 \$3 \$12 \$15 \$3,000 \$2,570 \$12,000 \$6,000	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840 \$12,000 \$6,000	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115 20 Units 1200 high Steel Barrier with Posts at 2m Centres
3.6 3.7 3.8 3.9 4 4.1 1 2 3 4 5	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units Insitu Concrete Headwall to Suit Twin 1200x900 RCBC Concrete Trash Deflector Grouted Stone Pitching	m3 m2 m3 m3 item Im item item item m2	230.9 818.1 1382.7 186.5	\$75 \$3 \$12 \$15 \$3,000 \$2,570 \$12,000 \$6,000 \$150	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840 \$12,000 \$6,000 \$900	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115
3.6 3.7 3.8 3.9 4 4.1 1 2 3 4 5 6 7	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units Insitu Concrete Headwall to Suit Twin 1200x900 RCBC Concrete Trash Deflector Grouted Stone Pitching New Headwall Barrier	m3 m2 m3 m3 item item item item item item item item	230.9 818.1 1382.7 186.5 1 1 12 1 1 6 11	\$75 \$3 \$12 \$15 \$3,000 \$2,570 \$12,000 \$6,000 \$150 \$350	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840 \$12,000 \$6,000 \$900 \$3,850	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115 20 Units 1200 high Steel Barrier with Posts at 2m Centres
3.6 3.7 3.8 3.9 4 4.1 1 2 3 4 5 6 7	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units Insitu Concrete Headwall to Suit Twin 1200x900 RCBC Concrete Trash Deflector Grouted Stone Pitching New Headwall Barrier South of Existing Culvert Demolish Existing Southern Headwall & Make Good, Match new 1200 x 900 RCBC	m3 m2 m3 m3 item lm item jtem jtem m2 lm	230.9 818.1 1382.7 186.5 1 1 12 1 1 6 11	\$75 \$3 \$12 \$15 \$3,000 \$2,570 \$12,000 \$6,000 \$150 \$350	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840 \$12,000 \$6,000 \$900 \$3,850	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115 20 Units 1200 high Steel Barrier with Posts at 2m Centres Sheet 102/115
3.6 3.7 3.8 3.9 4 4.1 1 2 3 4 5 6 7	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units Insitu Concrete Headwall to Suit Twin 1200x900 RCBC Concrete Trash Deflector Grouted Stone Pitching New Headwall Barrier South of Existing Culvert Demolish Existing Southern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units	m3 m2 m3 m3 item item item item item item item item	230.9 818.1 1382.7 186.5 1 1 12 1 1 6 11	\$75 \$3 \$12 \$15 \$3,000 \$2,570 \$12,000 \$6,000 \$150 \$350 \$3,000 \$2,570	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840 \$12,000 \$6,000 \$900 \$3,850 \$3,000 \$47,031	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115 20 Units 1200 high Steel Barrier with Posts at 2m Centres
3.6 3.7 3.8 3.9 4 4.1 1 2 3 4 5 6 7	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units Insitu Concrete Headwall to Suit Twin 1200x900 RCBC Concrete Trash Deflector Grouted Stone Pitching New Headwall Barrier South of Existing Culvert Demolish Existing Southern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units	item item item item item item item item	230.9 818.1 1382.7 186.5 1 1 12 1 1 6 11 1 18.3 4	\$75 \$3 \$12 \$15 \$3,000 \$2,570 \$12,000 \$6,000 \$150 \$350 \$3,000 \$2,570 \$1,000	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840 \$12,000 \$6,000 \$900 \$3,850 \$47,031 \$4,000	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115 20 Units 1200 high Steel Barrier with Posts at 2m Centres Sheet 102/115
3.6 3.7 3.8 3.9 4 4.1 1 2 3 4 5 6 7 4.2 1 2	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units Insitu Concrete Headwall to Suit Twin 1200x900 RCBC Concrete Trash Deflector Grouted Stone Pitching New Headwall Barrier South of Existing Culvert Demolish Existing Southern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units e/o for Tapered Units Insitu Concrete Bend	item item item item item item in item item item item item	230.9 818.1 1382.7 186.5 1 1 1 2 1 1 6 11 1 18.3 4	\$75 \$3 \$12 \$15 \$3,000 \$2,570 \$12,000 \$6,000 \$150 \$350 \$3,000 \$2,570 \$1,000 \$8,000	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840 \$12,000 \$6,000 \$900 \$3,850 \$47,031 \$4,000 \$8,000	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115 20 Units 1200 high Steel Barrier with Posts at 2m Centres Sheet 102/115
3.6 3.7 3.8 3.9 4 4.1 1 2 3 4 5 6 7	65mm Rock Ballast A34 Geotextile Selected Backfill, to 95% 100mm Topsoil respread Subtotal Section 3 Drainage structures, Gabions / Walls Creek Culvert North of Exiting Culvert Demolish Existing Northern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units Insitu Concrete Headwall to Suit Twin 1200x900 RCBC Concrete Trash Deflector Grouted Stone Pitching New Headwall Barrier South of Existing Culvert Demolish Existing Southern Headwall & Make Good, Match new 1200 x 900 RCBC New Twin 1200 x 900 RCBC, 1.2m units	item item item item item item item item	230.9 818.1 1382.7 186.5 1 1 12 1 1 6 11 1 18.3 4	\$75 \$3 \$12 \$15 \$3,000 \$2,570 \$12,000 \$6,000 \$150 \$350 \$3,000 \$2,570 \$1,000	\$17,316 \$2,454 \$16,592 \$2,798 \$68,559 \$3,000 \$30,840 \$12,000 \$6,000 \$900 \$3,850 \$47,031 \$4,000	allowed additional 0.5m for each side utilise stockpiled spoil Sheet 102/115 20 Units 1200 high Steel Barrier with Posts at 2m Centres Sheet 102/115

1 of 3



SOUTH PARK LANDS STORMWATER MANAGEMENT

COST ESTIMATE FOR PARK 20 EMBANKMENT PRELIMINARY DESIGN

ITEM	DESCRIPTION		QUANTITY	COSTPLAN QTYS AND CO	OST AMOUNT	COMMENTS
7	New Headwall Barrier	lm	QUANTITY 11	\$350	\$3,850	COMMENTS 1200 high Steel Barrier with Posts at 2m Centres
•	Now Headwall Barrier			φοσο	φο,οοο	1250 High Occor Barrier with 1 03to at 2111 Ochiles
	East Creek Enlargement					
4.3	Upstream Upstream					Sheet 103/115
1	Detailed Excavation	item	1	\$2,700	\$2,700.00	Sheet 103/113
2	Localised Backfill	item	1	\$3,200	\$3,200.00	
3	A34 Geotextile				\$3,200.00	
		m2	26.46	\$3 *63		O 2m uida
4	Sand Bedding to Aggregate Pipe	m3	0.21	\$63	\$13	0.3m wide
5	Aggregate Bedding to Slotted pipe(13mm)	m3	0.63	\$75	\$47	0.3m wide
6	160mm CLASS 400 Slotted Drain coil pipe	lm	14	\$25	\$350	to IP1
. 7	150mm PVC DWR Riser with Screw Cap	lm	1.8	\$75	\$135	Approx. 1.8m each
8	Light Duty Cover and Frame to 150mm PVC risers	no	1	\$800	\$800	
9	300mm Rock Filled Reno Mattress	m2	19	\$185	\$3,515	
10	Rock Filled Gabion at end of reno matt	m3	2	\$350	\$700	1x1x2
11	New Headwall Barrier	lm	8	\$350	\$2,800	1200 high Steel Barrier with Posts at 2m Centres
4.4	<u>Downstream</u>					Sheet 103/115
1	Detailed Excavation	item	1	\$2,400	\$2,400.00	
2	Localised Backfill	item	1	\$2,800	\$2,800.00	
3	A34 Geotextile	m2	26.46	\$3	\$79	
4	300mm Rock Filled Reno Mattress	m2	20	\$185	\$3,700	
5	Rock Filled Gabion at end of reno matt	m3	2	\$350	\$700	1x1x2
6	New Headwall Barrier	lm	8	\$350	\$2,800	
J				ψοσο	Ψ2,500	
1 F	Culvert & HW					Sheet 102/115
4.5		m2	535.68	¢ 4 E	\$24.405.60	
1	Detailed Excavation	m3		\$45	\$24,105.60	Stepped Batter Slope @ 1mx1m
2	New Twin 1800 x 1200 RCBC, 1.2m units	lm 	55.8	\$2,570	\$143,406	94 Units
3	e/o for Tapered Crown Units	item	1	\$5,000	\$5,000	94 Units
. 4	Insitu Concrete Headwall to Suit Twin 1800x1200 RCBC	no	2	\$12,000	\$24,000	
5	Backfill	m3	425	\$15	\$6,377.94	with excavated spoil
4.6	NEW TELSTRA SERVICE, CONCRETE ENCSED CREEK CROSSING	lm	12.4	\$2,000	\$24,800	Crossing at Chainage 265 (MC10)
	Southern Creek & Drain Enlargement					
4.7	Extend Existing headwall					Sheet 104
1	Detailed Excavation	m3	10.5	\$125	\$1,312.50	
2	A34 Geotextile	m2	53.2	\$3	\$160	
3	Rock Filled Gabions	m3	21	\$350	\$7,350	
4.8	Existing Creek Discharge					Sheet 104/116
1	A34 Geotextile	m2	26	\$3	\$78	
2	300mm Thick Stone Pitching (100-150mm rock spalls)	m2	22.4	\$150	\$3,360	5.6m(avg) x 4m
	Cooling Trick Storic Fitching (100 Foothin Foot Spails)	1112	22.7	Ψισο	ΨΟ,ΟΟΟ	o.omavg, x an
	Subtotal Section 4				\$408,140	
5	MISC					
			400	***	*****	0
5.1 5.2	200x300H Concrete Edge Beam Reinstate Footpath over Embankment with AC to council spec	lm m2	100 70	\$90 \$125	\$9,000 \$8,750	Chain 0-100 35m x 2m wide
J. <u>L</u>	1 constant 1 cooperation and animals with AC to country spec	1112	, 0	ΨΙΖΟ	ψ0,730	OSIT A LITTER WINDS
	Landscaping works					
5.3	Remove Existing Path	lm 0	122	\$30.00	\$3,660	
5.4 5.5	Primary Pathway - 3m Wide Sealed Secondary Path - 1.8m Wide Rubble	m2 m2	1332 559.8	\$64.54 \$40.47	\$85,963 \$22,654	
5.6	Dryland Grassing	m2	20450	\$40.47 \$1.65	\$33,743	Hydro seed
5.7	New Trees	no	148	\$90.00	\$13,320	Assume 40 Litre
5.8	Establishment / Maintenance for Landscaping works	item	1	\$42,580	\$42,580	Assume 1 yr. maintenance period
	0.11.110.5				\$219,670	
					Ψ213,070	
	Subtotal Section 5				1	
6	Reinstatement and finishing works					***************************************
6		item	1	\$24,000	\$24,000	
	Reinstatement and finishing works Site clean-up and demobilisation	item	1	\$24,000		
	Reinstatement and finishing works	item	1	\$24,000	\$24,000 \$24,000	
	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6	item	1	\$24,000	\$24,000	\$1,11
	Reinstatement and finishing works Site clean-up and demobilisation	item	1	\$24,000		\$1,11
6.3	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6 SUBTOTAL 1 - 6	item	1	\$24,000	\$24,000	\$1,11
6.3	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6	item	1	\$24,000	\$24,000	\$1,11
7	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6 SUBTOTAL 1 - 6 Contractors Offsite OH and Margin				\$24,000 \$1,329,952	
6.3	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6 SUBTOTAL 1 - 6	item	8%	\$24,000 \$1,329,952	\$24,000	
6.3	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6 SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin				\$24,000 \$1,329,952 \$106,396.19	
6.3	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6 SUBTOTAL 1 - 6 Contractors Offsite OH and Margin				\$24,000 \$1,329,952	
7 7.1	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6 SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin				\$24,000 \$1,329,952 \$106,396.19	
7 7.1 8	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6 SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin TOTAL CONSTRUCTION COSTS CLIENT COSTS	%	8%	\$1,329,952	\$24,000 \$1,329,952 \$106,396.19 \$1,436,349	allowance for offsite OH and profit
7 7.1	Reinstatement and finishing works Site clean-up and demobilisation Subtotal Section 6 SUBTOTAL 1 - 6 Contractors Offsite OH and Margin Offsite OH and Margin				\$24,000 \$1,329,952 \$106,396.19	

2 of 3



SOUTH PARK LANDS STORMWATER MANAGEMENT

COST ESTIMATE FOR PARK 20 EMBANKMENT PRELIMINARY DESIGN

				COSTPLAN QTYS AND COS	Т	
ITEM	DESCRIPTION		QUANTITY	RATE	AMOUNT	COMMENTS
8.3	Investigations and design	%	12%	\$1,436,349	\$172,362	Including design verification works
	Project and contract management	%	8%	\$1,436,349	\$114,908	
8.5	Community engagement and liaison	%	2%	\$1,436,349	\$28,727	
8.6	Land acquisition					EXCLUDED FROM THIS ESTIMATE
	TOTAL CLIENT COSTS		30%		\$430,905	

	BASE PROJECT COST				\$1,867,253	
9 9.1 9.2	RISK AMD OPPORTUNITY Inherent Risk Contingent Risk	%	7% 15%	\$1,867,253 \$1,867,253	\$280,088	This is the uncertainties in the known or planned scope of the project. These are risks due to unmeasured items and are conditional, i.e. they may or may not happen. Note; Contingent Risk does not cover changes to the project objectives
	TOTAL RISK ALLOCATION				\$410,796	
	TOTAL ESTIMATE PROJECT COST				\$2,278,049	
	TOTAL				\$2.3	(million rounded)

	IMPORTANT NOTES AND KEY ASSUMPTIONS
1	Excludes GST
2	Costs are current as at Q1, 2015 and excludes escalation
3	Based on TONKIN Preliminary concept design FOR Park 20 Embankment20130167_Sht100-116-Rev 3.pdf
4	Excludes Land acquisition costs (if applicable)
5	Assumes no Hardscaping, path lighting or structures
6	This estimate has been prepared solely for BHKC stormwater authority, C/Othe City of Unley . Under no circumstances shall it be passed onto any third parties without the written consent of Costplan Pty Ltd